

## Republic of the Philippines

## DEPARTMENT OF EDUCATION

Region XI

# CITY SCHOOLS DIVISION OF DIGOS CITY

Digos City

# REQUEST FOR QUOTATION



19-11-168	
RFQ No.	
25-Nov-19	
Dute	

Company Name	
Address	
Contact No	
TIN No.	

Please quote your lowest price on the item/a listed below, subject to the General Conditions, stating the shortest time of delivery and submit your quotation duly signed by your representative.

For and in the absence of the BAC Champerson.

MELANIE P. ESTACIO, Ph.D. BAC C (IAIRMAN

BAC VICE CHAIRMAN

#### NOTE:

- 1 ALL ENTRIES MUST BE LEGIBLY WRITTEN
- 2. DELIVERY PERIOD MUST BE WITHIN 10 DAYS UPON RECEIPT OF P.O.
- 3 PRICE VALIDITY MUST BE WITHIN THIRTY (30) DAYS
- 4 PAYMENT ITRM. WITHIN 30 DAYS
- 5 BIDDERS MUST SUBMIT CERTIFIED PROTOCOPY OF THE FOLLOWING

### REQUIRED DOCUMENTS TOGETHER WITH THE REQ

- a) Mayor's/Business Permit
- b) PhilGEPS Registration
- c) Income/Business Tax Return
- d) Omnibus Sworn Statement (ORIGINAL)
- NOTE: For CY 2019, Ind. lers shall submit these documents to DepEd Digos City Division only ONCE
- 6 Approved Budget: Php 115,000 00

#### EARLURE TO DO SO WILL MEAN DISQUALIFICATION OF YOUR BID PROPOSAL

TEM NO.	(FAILURE TO DO SO WILL MEAN DISQUALIFICATION OF	UNIT	QTY.	UNIT PRICE	TOTAL PRI
1	Installation of Close Circuit TV (CCTV) System with	lot	1		
	Local Area Network Cabling				
	Hardware Specifications:				
	16 Channel DVR 2 slots HDD Drive				
	Centralize and or Individual Power Supply				
	Coaxial Cable, UTP, or STP Cat 5e Network Cable and				
	Fiber Optic Cable				
	43 inches TV Monitor		100 mm		
	10 pcs- 3 MP or Higher Pixel Cameras				
	4 GB HDD Storage				
	PVC Pipe for ground cabling and molding for wall and ceiling				
	cabling				
	2 units of 16-Port Gigabit Ethernet Switch with at least 2		1		
	gigabit fibre optic port				
	and other materials needed in the installation				
	Scope of Work				
	Supply and Installation necessary CCTV Cameras, Cables				
	and Internet cables and its accessories in 4 building areas				
	Supply and Installation of DVR or Video Recorders, Monitors				
	and Power Supply				
	Supply and Installation Ethernet Switch and One Fibre Cable				
	Line thru ground piping (around 150 meters between 2 buildings)				
	End to end termination of all copper and fiber cables installed				
	Testing and Commisioning				
	·				
2002220	1 YEAR WARRANTY ON ALL PRODUCTS AND SERVICES				
			-	-	
			1		